5-5006

2004-17 Ford F150 4WD 3" Block Kit

RUGGED

Step by step instructions and checklist: Use the proper tools and safety equipment to perform all work. Torque all fasteners to proper specifications and double check work. Align your vehicle after installation.



Raise vehicle securely by frame and support axle with jack..



Work on one side at a time to prevent driveline damage. Remove lower shock Bolt



View of 4WD rear axle and leaf spring, note factory block



Loosen and remove factory u-bolt hardware.



Remove u-bolt nuts and lower plate.



Lower axle enough to remove factory block.



Install lift block with centering pin toward axle.



Raise axle and ensure locating pins are properly aligned.



Slide new u-bolts over leaf pack and bumpstop bracket.



Attach lower mounting plate with provided hardware.



Snug hardware down, lower vehicle on ground and torque.

FinalChecks&Adiustments

Post InstallationWarnings: Once the vehicle is loweredtothe ground, checkall parts which have rubber or urethanecomponents to insure proper torque. Torquewheelst ofactory specs. Move vehicle backwards and forwards ashort distance to allow suspension components to adjust. Turn the front wheels completely left then right and verify adequate tire, wheel, brake line, and ABS wire clearance. Test and inspects teering, brake and suspension components for tightness and proper operation. In spect brakes hoses and ABS lines for adequate slack at full extension. Failure to perform the post in spection checks may result in vehicle component damage and/or personal injury or death to driver and/or passengers. Test drive vehicle and re-check the torque of all fasteners and re-torque wheels on vehicle.

WheelAlignment/HeadlampAdjustment:

It is necessary to havea properandprofessionalwheel alignment performedbya certifiedalignmenttechnician. Alignthe vehicle to factory specifications. It is recommended that your vehicle alignment bechecked after any off-roaddriving. In addition to your vehicle alignment, for your safety and others, it is necessary to check and adjust your vehicle head lamps for proper aim and alignment.

VehicleRe-TorqueandSafetvInspection:

Upon completion of allservices and adjustments performed on your vehicle, and within 50 miles of driving, check to ensure all fasteners and hardware are properly torqued to specification as noted in the vehicles factory service manual.

www.ruggedoffroad.com 888.670.2252